FOREST DEPARTMENT.

BANGALORE DISTRICT.

Resale Notification dated 1st April 1940.

It is hereby notified for general information that the exclusive right of collecting Minor Forest Produce on all Government unoccupied lands, Amrit Mahal Kavals, State Forests, Reserved Lands and Plantation from the date of confirmation of the sale to 30th June 1940, in the undermentioned Taluks of the Bangalore District will be sold by public auction by the District Forest Officer, Bangalore District, at the risk of the original lessees as they have failed to pay up the khist amount.

Unit No.	Taluk	Place of sale	Date of sale
1	Kankanhalli	District Forest Office, Seshadri Road, Bangalore.	Monday, 22nd April 1940 at 3 P.M.
2	Magadi		
3	Nelamangala		
4	Bangalore		
5	Closepet		
6	Channapatna		
7	Maradi & Nux Vomica seeds in Bangalore District.		

P. KRISHNASWAMI RAO,
District Forest Officer.

ENGINEERING DEPARTMENT.

BUILDINGS DIVISION, BANGALORE.

Notification dated 30th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 22nd April 1940 up to 2 P.M. for constructing ten Married Men's Quarters in Mysore Transport, Hebbal, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained on payment of annas 4 from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 625 (six hundred and twenty-five only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing ten Married Men's Quarters in Mysore Transport, Hebbal, Bangalore in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintendent Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Rates must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any rates quoted at so much percentage less or more than estimated rate will not be accepted.

Tender for constructing Married Men's quarters in Mysore Transport, Hebbal, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement and carting the excavated earth to a distance not less than 50 yds. and refilling the excavated earth to the basement duly watering and tamping in layers of 6″ thick in all sides ..	C.yd.	..	44	
2	Burnt stone jelly concrete in lime mortar (jelly of 1″ to 1¼″ thick cubes) with the proportion of 1 part of lime to 2½ parts of sand and 4 parts of jelly for foundations laid in layers of 6″ thick with consolidation	C.ft.	..	294	
3	Size stone in clay for foundation the courses should not be less than 8″ high with bond stones at every 6′ apart with one line dressing at the faces and quoir dressing for basement	C.ft.	..	1,144	
4	Burnt brick in mud inserting bond stones	,,	..	2,534	
5	Burnt stone slabs 6″ thick, roughly dressed and fixed in mortar	S.ft.	..	222	
6	Burnt stone slabs 6″ thick, one line dressing on exposed faces and fixing	,,	..	80	
7	T. W. panelled doors with two shutters including iron fittings, etc.	,,	..	159	
8	T. W. windows with ¾″ iron bars panelled shutters and iron fittings, etc., complete	,,	..	71	
9	Roofing with R.C.C. 6″ thick as per standard specification and calculation	Sqr.	..	6·69	
10	Providing cement concrete chajja over doors and windows in front 3′ projecting 3″ to 2½″ thick ..	S.ft.	..	162	
11	R.C. ventilators including fixing charges	,,	..	24	
12	R.S. girder 9″×3″ including fixing charges, hoisting, carting, etc.	Cwts.	..	5	
13	Lime plastering walls	Sqr.	..	40·40	
14	White washing 2 coats as per plastering	,,	..	40·40	
15	Flooring with cement concrete 1½″ thick over 3″ lime concrete with red coloured cement plastering and smooth finish	Sqr.	..	5·71	
16	Cement drain with cement plastering on slab foundation.	R.ft.	..	47	
17	Painting to doors and windows with 2 coats of Lac Factory Green paint	Sqr.	..	40·03	
18	Providing and fixing R.C.C. slabs for partition walls, with coping and fixing	S.ft.	..	334	
19	Constructing over in kitchen with burnt brick in mud, and plastering with cover slab and chimney ..	No.	..	2	
20	Cement pointing to basement	Sqr.	..	3·70	
21	Constructing parapet wall of 1½′ height including and plastering all round and; etc., complete	R.ft.	..	91¼	
22	Providing mortar band alround	,,	..	91¼	
23	Providing mortar and pestle stones	L. S.	..	..	
24	Providing sinks and ovens in kitchen and bath as per instruction	,,	..	..	
25	Providing teakwood shelf planks with pegs ..		..	..	

M. K. RAJAM IYENGAR,
Executive Engineer.

MANDYA DIVISION.

Notification dated 30th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mandya Division, up to 12 NOON on 22nd April 1940, for restoring Thenginaghatta minor tank, Reg. No. 1137, Krishnarajpet Taluk.